

General Comparisons in Cost Per Square Foot Including Overhead and Profit

Unit Size based on 8" Height x 16" Length (except where noted)	2" Bed Depth	4" Bed Depth	6" Bed Depth	8" Bed Depth
THIN SET CERAMIC TILE ON C.M.U.				
Thin Set Ceramic 4-1/4" x 4-1/4" Tile on C.M.U.:				
C.M.U. installed (R042210.14-0050/0200/0300/0350)	5.65	5.95	6.80	7.40
Tile w/ Thin Set Adhesive (R093013.10-5400)	6.25	6.25	6.25	6.25
Mortar Set Adhesive, add (R093013.10-7300)	2.54	2.54	2.54	2.54
Total Square Foot Cost**	14.44	14.74	15.59	16.19
EPOXY PAINTED C.M.U.				
C.M.U. installed (R042210.14-0050/0200/0300/0350)	5.65	5.95	6.80	7.40
Block Filler (R099123.72-4000)	1.08	1.08	1.08	1.08
Epoxy Coatings min. to max. (R099656.20-0300/0400)	1.14-3.50	1.14-3.50	1.14-3.50	1.14-3.50
Total Square Foot Cost	7.87-10.23	8.17-10.53	9.02-11.38	9.62-11.98
CONCRETE BLOCK, DECORATIVE				
Ground Face (R042210.23-2600/2650/2700) Total Sq Ft Cost	N/A	10.25	11.85	13.25
Special Color (R042210.23-2900/2950) Total Sq Ft Cost	N/A	10.88-12.14	12.67-14.30	14.20-16.10
Add C.M.U. Waterproofing Sealer Ext. 2 coats (R099113.90-xxxx)	Brushed (R-0390/0400)=1.41 Rolled (R-0430/40)=0.94 Sprayed (R-0470/80)=0.83			
Add C.M.U. Interior Sealer (R099123.72-4100/3600/3620)	Silicone 2 coats sprayed=0.49 5 coats glaze sprayed > clear=1.10; > multicolor=1.54			
Add (R099123.72-8200/8300)	For sealer work between 8'-15' add+10%; above 15' add+20%			
PREFACED C.M.U.				
Glazed C.M.U.** (R042210.44-0100/0200/0250/0300)				
Total Square Foot Cost	13.65	14.05	14.85	15.95
STRUCTURAL GLAZED FACING TILE				
Structural Glazed Facing Tile** (R042126.10-0020 to 3150)				
Total Square Foot Cost (8" x 16" face size-8W Series)	13.60	14.50	18.25	20.50
(8" x 8" face size-4W Series)	14.85	15.10	18.45	24.50
(5-1/3" x 12" face size-6T Series)	16.45	17.90	23.00	28.00

* National averages taken from *Means Building Construction Cost Data 2007*, Copyright Reed Construction Data, Kingston, MA, 781-585-7880, All rights reserved.

** For epoxy joints (R042126.10-3300), add \$1.52.